A member of the Interpump Group

TMT FLOW SWITCH

Tri-Magnet Technology Inline Flow Switch




FEATURES

- · Micro-switch technology eliminates reed switch
- Activates with 1.25 GPM flow
- · Stainless Steel shuttle
- · Minimal pressure drop up to 12 gpm flow
- · Can be mounted in any position


SPECIFIC	ATIONS	
Part Number		100975
Maximum Operating Pressure Minimum Flow Required for Activation Maximum Operating Flow		5000 PSI
		1.25 GPM
		12.0 GPM
Operating Temperature Range		40 - 180 °F
Electrical Lead Length		48" - 18AWG
Switch Ratings	Max Switching Voltage	250 VAC
	Max Switching Current	5 AMPS
	Resistance with Leads	30 OHM
Ports	Inlet	3/8" x 18 NPT-F
	Outlet	3/8" x 18 NPT-F
Dimensions		3.91" x 1.4" x 2.95"
Weight		1.0 LBS
Materials	Brass, Stainless Steel, Plastic, Nickel-plated Neodymium	


EXPLODED VIEW

NOTE: When using this flow switch in a system containing a positive displacement pump, General **Pump** recommends the use of a safety relief device(s), correctly placed to protect all areas of the system.




DIMENSIONS AND WIRING SCHEMATIC















SERVICE INSTRUCTIONS

- 1. Remove external plumbing from device, as needed.
- 2. Remove "Cap" (510453)



3. Slide out "Shuttle Assy" (103135); if magnet is damaged or missing, replace device.



4. Observe "Shuttle Assy" and internal portion of "Body" (510456) for obstructions, hard-water deposits, or any other foreign debris. Remove via light scraping and/or compressed air.






5. If required, remove "Body" from plastic "Enclosures" (660137) and soak in CLR or similar solution to dislodge excessive build-up. QTY (5) "Screws" (201006) for "Enclosure" are TORX T10.



- 6. Rinse "Body".
- 7. Re-install "Body" into "Enclosures" as shown above, taking care to not damage. Tighten "Screws" until snug. Do not over-tighten.
- 8. Insert "Shuttle Assy", with rounded end first, into body. Align with grooves.



ROUNDED END FIRST

- 9. Install "Cap", torque to 100 in.lbs. (Replace "O-ring" (701014) as needed)
- 10. If possible, verify operation by activating "Shuttle" manually while observing continuity to leads. "Shuttle" should return to home position automatically.



11. Re-install device on equipment, test operation.

TROUBLESHOOTING

If device will not operate, verify:

- -Are magnets damaged or missing?
- -Is there an obstruction preventing shuttle from sliding?
- -Is "Shuttle Assy" in correct orientation?
- -Is the electrical switch operating correctly? (can be verified by checking continuity and activating shuttle/switch manually)





Ref 300770 Rev E 04-17

